Approximate estimate of quantities for restoring Boppagondanakoppa Tank R. No. 1070, Sorab Taluk.

No.	Description of work	Per	Quantity
	BUND AT R. L. 55·00		
1	Jungle clearing and scraping grass and cutting trenches to receive new earth.	Lump sum	
2	Earthwork including watering and tamping	C.yd.	4,234
3	Turfing front and rear slopes	S.yd.	5,325
4	Providing grade stones, including dressing, cutting figures fixing painting, etc., complete.	No.	16
5	Index stones	,,	16
6	Survey and constructive detail stone	,,	1
7	Bench mark stones	,,	2
8	Guage stone	,,	1
	SLUICE No. 1 AT R. L. 46·50.		
1	Earthwork excavation and refilling	C.yd.	57
2	Stone concrete in surki mortar	C.ft.	189
3	Burnt brick in surki mortar.	,,	244
4	Burnt stone slabs dressed 6" thick	S.ft.	69
5	Plastering with surki mortar	Sq.	2·00
6	Cutting uppet and lower orifices in slabs	Lump sum	
7	Fixing 9" dia. C. I. Pipes with cement pointing and carting from Shimoga (pipe supplied departmentally at Shimoga).	R.ft.	27
8	Providing teak wood plug and rod, etc., complete ...	Lump sum	
	SLUICE No. 2 AT R. L. 46·50.		
	Same as sluice No. I	...	...
	WASTE WEIR LEFT AT R. L. 50·00.		
1	Earthwork excavation	C.yd.	253
2	Surki concrete in surki mortar	C.ft.	787
3	Burnt brick in surki mortar	,,	914
4	Burnt stone slabs dressed 6" thick with joggle joints ...	S.ft.	462
5	Plastering with surki mortar wherever necessary ...	Sqr.	15·00
6	Rough stone work now with jelly packing	C.yd.	145
7	Unforeseen items such as clearing the approach in front and draft in rear, etc.	Lump sum	

M. A. SRINIVASACHARI,
Executive Engineer.

OFFICE OF THE DIRECTOR OF AGRICULTURE IN MYSORE, BANGLORE.

Notification No. I. D. 1856 of 27-28, dated 29th July 1927.

The undermentioned three old and unserviceable tents of this Department will be sold by public auction on the 23rd August 1927, at the Office of the Director of Agriculture in Mysore, Bangalore.

The sale will commence at 2 P.M., and the articles will be knocked down to the highest bidder without reserve on immediate payment. Purchaser will be allowed to take delivery of the articles as soon as the full amount of purchase money is paid on the spot, failing which, the articles will be resold at the risk of the first purchaser.

1. Single pole tents 2
2. Hill tent 1

G. H. KRUMBIEGEL,
Offg. *Director of Agriculture.*

From 4th August 1927, through this publication, I (K. N. Venkatesan, son of late Mr. K. Narayana Iyer, Amildar) have changed my full name to K. N. V. Esan, and all signatures of Esan hereafter and K. N. Venkatesan prior to this publication are identical and refer to the same person.

K. N. V. ESAN,
Trinapuri Vilas,
Chamundy Extension, Mysore.